Statement showing the approximate quantities of work for constructing One Block of Cooly Quarters and an Operator's Quarters with 2 units of Latrine at Maddur.

Serial No.	Items	Unit	Operator's Quarters	Cooly sheds	2 Units of Latrine
1	Earth work excavation and filling in basement.	Cyd.	24	18	8
2a	Concrete stone jelly in lime mortar ...	Cft.	306	219	...
b	Coursed rubble stone masonry in clay foundation and basement with bond stones in each course 6 ft. apart	"	547	440	260
c	Burnt brick in clay superstructure ..	"	1666	1512	...
d	Stone slabs 4" thick set in Lime mortar ...	Sft.	108	66	...
e	Stone slab 6" thick for pillars including polly cutting fixed complete.	"	..	12	...
f	Do 6" thick do ...	"	5	...	..
g	Chunam plastering two coats ...	Sqr.	44·06	29·75	9·82
h	Chunam pointing with thread lines ...	"	1·03	1·00	1·12
i	White and colour washing 2 coats ...	"	45·10	29·70	10·94
j	Constructing sinks in bath rooms ..	No.	1	2	..
k	Mortar and pestle fixed complete ...	"	1	2	...
l	6" plain cornice brick in mortar ..	Rft.	56	40	...
m	6" x 3" chunam patty over roof ...	"	12	18	...
3a	First class Mangalore tile roofing on teak wood reepers complete.	Sqr.	7·89	7·68	...
b	Ridge tile set in mortar	Rft.	24	25	...
c	Ventilating tiles set in mortar ...	No.	2	8	...
4a	Honney wood wrought and put up with 2 coats of wood oil.	Cft.	29·35	24·40	....
b	Teak wood doors with Honney wood battened shutters 1" thick with bolts and hinges complete.	Sft.	137	39	...
4c	Teak wood windows with Honney wood battened shutters 1" thick with bars, etc., complete.	Sft.	50	39	...
d	Teak wood ventilators	"	18	...	...
e	Teak wood planks 1" thick with wood oiling.	"	34	...	...
f	Chocolate painting two coats ...	Sqr.	4·78	1·00	...
5	Flooring on 3" concrete and cement plastering ½" thick finished smooth and even.	"	4·50	4·00	...
6	Binding wall 1·1/8' x ¾' brick in mortar and chunam plastered.	Rft.	56	40	...
7	Burnt bick in mortar superstructure ...	Cft.	...	...	392
8	Cement plastering ½" thick ...	Sqr.	....	...	1·58
9	Tar washing 2 coats	"	...	...	1·26
10	Flooring with 3" thick concrete and cement plastering ½" thick.	"	...	....	·76
11	Providing galvanised iron sheet tubs 12" x 6" with handles, etc., complete with tarring.	No.	...	...	6

V. R. COWSIK,
For *Chief Electrical Engineer.*

BANGALORE DIVISION.

Notification dated 27th January 1933.

Notice is hereby given that sealed quotations will be received at the Office of the Executive Engineer, Bangalore Division, up to2 P.M. on 15th February 1933, for Improving Isthur Amanikere Reg. No. 103 of Hoskote Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1934.

given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash as earnest money and be superscribed "Tender for Improving Isthur Amanikere Reg. No. 103 of Hosakote Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, carricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer, Bangalore Division, will be final and legally binding.

12. Quotations must be shown in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimate rate will not be accepted.

13. Any tender containing a conditional clause contrary to these requirements or making stipulations not provided for either in this advertisement or the abstract quantity will be summarily rejected.

Abstract of quantities.

No.	Items of work	Unit	Rate	Quantity	Remarks
	Bund		Rs.		
1	Cutting grips and clearing jungle ..	Grades		26	
2	Earth work to bund, watering and tamping with lead and lift.	C.yd.		12,353	
3	Lead and Consolidating earth work available from draft and approach clearing.	"		590	
4	New stone revetment	"		797	
5	Resetting old stone revetment	"		243	
6	Turfing	S.yd.		7,929	
7	Providing new grade stones with numbering and painting.	Each		27	
8	Do Index stones	"		27	
9	Do Registered No. stone ..	"		1	
10	Do B. M. stones	"		2	
11	Do Gauge stones	"		2	
12	Dismantling the existing rough stone apron at right.	C.yd.		21	
	Sluices.				
	Examining and repairing the barrel and constructing front and rear cistern with plug and locking arrangements, etc., complete.	Each L S.		2	
	Waste Weir				
1	Earth work excavation	C.yd.		590	
2	Burnt brick in surki mortar	C.ft.		774	
3	Plastering with surki mortar	Square		1·25	
4	Rough stone apron new	C.yd.		121	
5	Burnt stone slabs dressed	S.ft.		356	
6	Cutting jogle joints	Each		35	

TUMKUR DIVISION.

Abstract Notification dated 23rd January 1933.

Subject.—Project for constructing an anicut across the River Shimsha near Chandanahalli, Kunigal Taluk.

Attention of the public is drawn to notification calling for tenders for the above work in pages 107 and 108 of part VI of *Mysore Gazette*, dated 26th January 1933.

2. The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up to 3 P.M. of 20th February 1933.

3. An earnest money of Rs. 3,500 should accompany the tender.

A. TANDONI RAO,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification dated 27th January 1933.

The attention of the public is invited to the notice calling for tenders for the diversion of *Bangalore-Nilgiri Road at* 6—101 *near Nanjangud Bridge* published in detail on pages 68 and 69 of Part VI of the *Mysore Gazette*, dated 19th January 1933.

The last date of receiving the tenders has been extended to 12 noon on 10th February 1933.

Abstract Notification, dated 16th January 1933.

Tenders are invited for deviating Madras-Cannanore Road from Wellesly Bridge near Kirangur. For particulars, *vide* pages 66 and 67, Part VI of the *Mysore Gazette*, dated 19th January 1933.

K. NARAYANA IYENGAR
Executive Engineer.

PALACE MARAMATH OFFICE, MYSORE.

Abstract Advertisement dated 23rd January 1933.

The attention of the public is hereby invited to the advertisement on page 105 of Part VI of the *Mysore Gazette*, dated 26th January 1933, calling for tenders for constructing a tank at Devagally Kaval, Mysore Taluk.

Abstract Advertisement, dated 23rd January 1933.

The attention of the public is invited to the advertisement on page 106 of Part VI of the *Mysore Gazette*, dated 26th January 1933, calling for tenders for "constructing the basement and foundations for the East Fort Gate, Mysore.

N. V. BAPAT,
Palace Engineer,
Maramath Department.

MISCELLANEOUS DEPARTMENTS.

GOVERNMENT GARDENS DEPARTMENT.

Notice dated 25th January 1933.

It is hereby notified that Tamarind, Honge, Jak, Cocoanut and other crops in the following grounds will be sold by public auction at the Cubbon Park Nursery, at 10 A.M. on 11th February 1933 :—

1. Cubbon Park.
2. Kumara Park.
3. Ballabrooie.
4. Senior Surgeon's Office.
5. Central College.
6. Intermediate College.
7. District Office.
8. Revenue Survey Office.
9. Victoria Hospital.
10. Vaccine Institute.
11. Executive Engineer's Office.
12. New Public Offices.
13. Chemical Examiner's Office.

1. Each bidder is required on demand to deposit a sum of Rs. 10 as earnest money before he is permitted to bid; this amount will be returned to him at the close of the sale, if his bid be not accepted.

2. The highest bidder who will be the purchaser should, on the spot, deposit 50 per cent of the amount due by him and pay up the balance within 2 days. In default thereof the crop will be resold at his risk without his participating in any profit that may accrue.